



SINGAPORE STANDARD

Code of practice for earthworks





CP 18: 1992 (ICS 93.020)

SINGAPORE STANDARD

Code of practice for earthworks

All rights reserved. Unless otherwise specified, no part of this Singapore Standard may be reproduced or utilised in any form or by any means, electronic or mechanical, including photocopying and microfilming, without permission in writing from SPRING Singapore at the address below:

Standards SPRING Singapore 1 Fusionopolis Walk, #01-02 South Tower, Solaris Singapore 138628

Email: standards@spring.gov.sg

This Singapore Standard having been approved by the Construction Industry Practice Committee was endorsed by the Standards Council on 22 December 1992.

First published, 1981 First revision, 1992

The Building and Construction Industry Practice Committee appointed by the Standards Council consists of the following members:

		Name	Organisation
Chairman	:	Mr Lam Siew Wah	Standards Council
Secretary	:	Ms Tan Sock Cheng	Singapore Institute of Standards and Industrial Research
Members	:	Mr Tan Tian Chong	Construction Industry Development Board
		Mr Heng Hua Jee	Housing Development Board
		Mr Harry Wong K C	Ministry of Labour
		Mr Tan Siong Leng	Public Works Department
		Mr Paul Chain	Singapore Construction Association Limited
		A/Prof J Alum	Nanyang Technological University
		Dr Gary Ong Khim Chye	National University of Singapore
		Engr Chee Keng Yam	Association of Consulting Engineers, Singapore
		Engr Ang Chee Keong	Institution of Engineers, Singapore
		Mr Paul Low	Singapore Institutes of Architects
		Mr Gilbert Tan Peng Cheng	Singapore Manufacturers' Association

The Technical Committee appointed by the Construction Industry Practice Committee and responsible for the preparation of this standard, consists of representatives from the following organisations:

		Name	Organisation
Chairman	:	Mr R Radhakrishnan	Individual Capacity
Deputy Chairman	:	A/Prof S D Ramaswamy	National University of Singapore
Secretary	:	Robin Low	Singapore Institute of Standards and Industrial Research
Members	:	Dr A J Dutt (up to December 92)	Institution of Engineers, Singapore
	Mr Goh Tock Eng		Ministry of the Environment
		Mr Hee Ah Mui	Jurong Town Corporation
		Mr Heng Yee Siang	Housing Development Board
		Mr Lim Beng Hock	Singapore Contractors Association Limited
		Mr Lim Jit Ming (up to Jul 92)	Public Works Department
		Mr Khor Poh Hwa (w.e.f. Jul 92)	Public Works Department
		Mr Wan Tong Wah	Ministry of Labour
		A/Prof Yong Kwei Yew (w.e.f Dec 92)	Institution of Engineers, Singapore

CONTENTS

										Page
Forewo	ord -	-	-	-	-	-	-	-	-	7
				CODE	OF PRA	CTICE				
1.	Scope -	-	-	-	-	-	-	-	-	8
Section	n One. Cutt	ings and e	mbank	ments, g	grading a	and lev	elling			
2.	Site condition	ons and inv	estinati	one	_	_	_	_	_	8
2.1	Preliminary				_	_	_	_	_	8
2.2	Ground exp		- 01 1116	- Project	_	-	-	-	-	9
2.3	Description		cation		- und rooks		-	-	-	11
2.4	Field and la			OI SOIIS a	ina rocks	5 -	-	-	-	
2.5				-	•	-	-	-	-	12
	Report on in			- 4 4! -	<u>-</u>	-	-	-	-	12
2.6	Further inve					-	-	-	-	12
2.7	Economic a					-	-	-	-	12
2.8	Risks of fail	ure and acc	eptano	e of defo	ormation	-	-	-	-	18
2.9	Cuttings	-		-	-	-	-	-	-	18
2.10	Factors gov						-	-	-	19
2.11	Modes of fa	ilure of cutt	ings ar	nd natura	l slopes	-	-	-	-	26
2.12	Methods of	analysis of	stabilit	y of slope	es	-	-	-	-	28
2.13	Design -	-	-		-	-	-	-	-	33
2.14	Monitoring (of slopes	-	-	-	-	-	-	-	39
3.	Embankmei	nts and gen	eral filli	ing	-	_	-	_	-	41
3.1	General fact	tors affectin	g the c	lesign of	the emb	ankme	nts	-	-	41
3.2	Strength an							ill		
	materials	-	-	-	_	-	-	_	-	41
3.3	Design of e	mbankment	S	-	-	-	_	_	_	43
3.4	Drainage	-	_	_	_	_	_	_	_	44
3.5	Special site	conditions	affectir	na amhar	kment o	r aana	ral fill de	eian		45
3.6	Suitability o			ig embai	IKITICITE O	i gene	iai iiii ui	sayıı	-	
5.0	Oullability O	i materiais i	Oi iiii	-	-	-	-	-	-	47
4.	Excavation	and filling	-	-	-	-	-	-	-	48
4.1	Planning	-	-	-	-	-	-	-	-	48
4.2	Preparation	of site	-	-	-	-	-	-	-	50
4.3	Excavation	-	-	-	-	-	-	-	-	51
4.4	Earth-movin	ıa -	_	-	_	-	-	_	-	52
4.5	Deposition a		na	-	-	_	_	_	_	52
4.6	Control -	-	···ອ -	_	_	_	_	_	_	53
4.7	Inclement w	eather duri	na con	etruction	_	_			_	55
4.8	Haul roads	-	ng con	Sti uction	_	-	_	_	-	
4.9	Advanced e	orthworks	-	-	-	-	-	-	-	55
			-	-	-	-	-	-	-	55
4.10	Stage const		-	-	-	-	-	-	-	56
4.11	The disposa	ii ot spoil	-	-	-	-	-	-	-	56
5.	Compaction	۱ -	-	-	-	-	-	-	-	56
5.1	General	-	-	-	-	-	-	-	-	56
5.2	Test for con	npaction of	earthw	orks	-	-	-	-	-	57

							Page
5.3	Methods of compaction -	-	-	-	-	-	57
5.4	Soil compaction characteristics -	-	-	-	-	-	57
5.5	Control of compaction in the field	-	-	-	-	-	60
5.6	Compaction adjacent to structures	-	-	-	-	-	61
6.	The operation of construction plant for	earthwo	rks	-	-	-	61
6.1	Classification of plant	-	-	-	-	-	61
6.2	Particular factors affecting earth-moving	plant	-	-	-	-	62
6.3	Preparation for excavation -	-	-	-	-	-	63
6.4	Excavation and earth-moving plant	-	-	-	• -	-	64
6.5	Compaction equipment	-	-	-	-	-	64
6.6	Specialist plant and equipment -	-	-	-	-	-	65
6.7	Safety measures	-	-	-	-	-	65
7.	Maintenance and protection of slopes	-	_	-	-	-	65
7.1	General	-	-	-	-	-	65
7.2	Maintenance of slopes	-	-	-	-	_	65
7.3	Sources of erosion	-	-	-	-	_	67
7.4	Methods of protection	_	-	_	-	-	68
7.5	Remedial works after slope failure	-	-	-	-	-	69
Section	n Two. Trenches, pits and shafts						
8.	Design considerations	_	-	-	-	_	71
8.1	Site investigation	-	_	-	-	-	71
8.2	Ground conditions	-	-	-	-	-	72
8.3	The design of stable slopes and suppor	ts to ex	cavatio	ons	-	-	74
8.4	Practical considerations -	-	-	-	-	-	76
9.	Construction procedure -	-	-	-	-	-	78
9.1	Temporary support of excavations	-	-	-	-	-	78
9.2	Backfilling	-	-	-	-	_	84
9.3	Support of excavation by diaphragm wa	alls or c	ast-in-p	lace bo	ored pile:	s -	85
10.	Trenches	_	_	_	-	<u></u>	85
10.1	Construction methods	_	-	_	-	_	85
10.2	Statutory obligations	_	_	-	-	-	86
10.3	Excavation procedure	_	-	_	-	_	86
10.4	Mechanical excavation of trenches	_	_	-	-	_	87
10.5	Hand excavation of trenches -	_	_	-	_	_	87
10.6	Methods of dewatering trenches	-	-	_	-	_	88
10.7	Installation of permanent work or mater	ials in ti	renches	s -	-	_	88
10.8	Backfilling and reinstatement of surface		-	-	-	-	88
11.	Pits and shafts	_	_	_	_	_	89
11.1	General	_	_	_	-	_	89
11.2	Methods of support of excavations	_	_	_	_	_	89
11.3	Drainage	_	_	_	_	_	89
11.4	Striking of supports and backfilling	_	_	_	_	_	89
11.5	Alternative methods of sinking -	_	_	_	_	-	89
11.6	Use of ground treatment processes	_	_	_	_	_	90
_							

								Page
12.	Excavation in rock -	-		-	-	-	-	91
12.1	General	-	-	_	-	-	-	91
12.2	Rock excavation by mechanica	l or hand	method	ds	-	-	_	91
12.3	Rock excavation by drilling and			-	-	-	-	91
12.4	Removal of loosened rock	-	_	-	_	_	_	92
	Three. Safety precautions							-
00001	Three. Gulety preductions							
13.	General	-	-	-	-	-	-	92
13.1	Precautions against incidental I	nazards	-	-	-	-	-	92
13.2	Personal protective apparel	-	-	-	-	-	-	92
13.3	Protection against rain -	-	-	-	-	-	-	93
13.4	Environmental safety -	-	-	-	-	-	-	93
13.5	Safe means of access and egre	ess	_	_	-	-	-	93
13.6	Falls of person and material	•	_	_	-	_	_	94
13.7	Lighting	_	_	_	_	-	_	94
13.8	Maintenance	-	_	_	_	-	_	94
13.9	Ventilation	_	_	_	_	_	_	94
13.10	Site transport	_	_	_	_	_	_	95
10.10	one transport	_	_	-	_	_	-	90
		AP	PENDIX	ζ				
A.	Definitions of terms used in this	Singapo	ore Stan	dard	_	_	_	120
		0 .						
		Τ.	ABLES					
1.	British soil classification system	for engi	neering	purpose	s and fie	eld		
	identification	-	-	-	-	-	-	14
2.	Field characteristics of soils an				earthwo	rks	-	16
3.	Design of slopes in rock cutting				-	-	-	20
4.	Typical compaction characteris	tics for n	atural so	oils, rock	s and			
	artificial materials used in earth	works co	nstruction	on	-	-	-	58
5.	Sources of advice for each res	pective h	azard	-	-	-	-	93
		FI	GURES					
1.	Short and long term stability of	cutting a	and emb	oankmen	t slopes	_	-	96
2.	Types of rotational slide	-	_	_	. o.opoo -	_	_	97
3.	Successive rotational slide	_	_	_	_	_	_	98
4.	Multiple retrogressive slide		_	_	_	_	_	98
5.	Slab slide			_		_	_	98
6.	Block slide	-	-	•	-	-	-	
		-	-	-	-	-	-	98
7.	Wedge failure	-	-	-	-	-	-	99
8.	Toppling failure	-	-	-	-	-	-	99
9.	Fall		-	-	-	-	-	99
10.	Slip circle analysis (undrained						-	100
11.	Slip circle analysis (undrained	shear stre	ength S _u	, varies l	aterally a	and		400
40	with depth)		<u>.</u> (\)	-	-	-	-	100
12.	Slip circle analysis (effective str			-	-	-	-	100
13.	Effect of tension cracks on slop	oe stabilit	:y	-	-	-	-	101

				Page
14.	Non-circular slide on weak soil layer	_	_	101
15.	Planar slide on infinite slope stability analysis	-	-	101
16.	Steep soil slope retained by ground anchors	-	-	102
17.	Unstable rock slope stabilised by rock bolts	_	-	102
18.	Slab slide stabilized by dowel bolts	-	-	102
19.	Reinforced earth	-	-	103
20.	Soil nail support system	-	-	103
21.	Components of a typical geocomposite drain	-	-	104
22.	Variation of unconfined compressive strength with moisture co	ntent		
	for typical local fill soils	-	-	105
23.	Envelope of strut loads on braced excavation	-	-	106
24.	Water-bearing permeable soils : seepage and uplift -	-	-	106
25.	Typical single or centre waling poling frame	_	-	107
26.	Close poling with tucking frames	-	-	108
27.	Support of deep excavation by horizontal sheeting and soldier	piles	-	109
28.	Trench excavation using steel trench sheets as runners -	· -	-	110
29.	Typical medium-depth trench with steel sheet piling in bad gro	und	-	114
30.	Wide and deep trench using steel sheet piling	-	-	114
31.	Blockings	-	-	115
32.	Trenches with sloping sides	-	-	115
33.	Methods of using engineering fabric in design/construction			
	of underdrains	-	-	116
34.	Method of lowering long steel pipes by use of temporary strutt	ing	-	117
35.	Method of excavating isolated pits and shafts	-	-	118
36.	Rock excavation by drilling and blasting : general excavation	-	-	119
37.	Rock excavation by drilling and blasting; pits and shafts	-	. <u>-</u>	119

SINGAPORE STANDARD

CODE OF PRACTICE FOR EARTHWORKS

FOREWORD

This Code of Practice was revised by the Technical Committee under the direction of the Construction Industry Practice Committee.

In general, this Code has been drawn up in relation to conditions existing in the Republic of Singapore.

The Code necessarily describes basic methods, some of which are traditional, and it has not been feasible to incorporate all the latest developments. For information on these, and particularly in regard to more complex and novel methods, reference should be made to relevant publications. It is recommended that when the consequences of a failure might be serious, expert advice should be obtained on problems involving the stability of earthworks.

At the same time, this Code necessarily recommends the adherence to the current regulations - The Factories Act; Building Operations and Works of Engineering Construction Regulations, The Factories (Safety Committee) Regulations, and The Water Pollution Control and Drainage Act.

This Code omits the recommendations on drilling and blasting as the use of explosives would be governed by Statutory Regulations.

The figures published in this Code are schematic and for illustration purposes only. They are not intended to show design details or use of particular materials.

The revision of this standard was based on BS 6031 : 1981 and is reproduced by permission of BSI, 2 Park Street, London W1A 2BS England.

Acknowlegement is made for the use of information from the British Standard and the specific contributions by the Sewerage and Drainage Departments, Ministry of the Environment and the Factory Inspectorate, Ministry of Labour.

NOTE

- Singapore Standards are subject to periodical review to keep abreast of technological changes and new technical developments. The revisions of Singapore Standards are announced through the issue of either amendment slips or revised editions.
- 2. Compliance with a Singapore Standard does not exempt users from legal obligations.